



Investments in refinery capacities in Serbia


September 2016
Belgrade, Energy community
Vladimir Gagic, NIS, Refinery

Presentation content




1. Refinery history
2. Refinery today
3. Strategy and development
4. Key investments
5. Conclusion

History of refinery



*Rules on technical and other requirements for liquid fuels of petroleum origin Fig. Gazette of RS, no. 123/2012 of 28/12/2012

Refinery today. Key competitors



Source: NIS, workgroup analysis * Nelson index after refinery upgrade



Refinery today. Key business drivers



Margins under pressure

- competition
- regulated prices → market related prices


Mogas / diesel imbalance

- need for max upgrading/conversion capacity
- need for export options

Product quality pressure

- Eurograde quality
- GHG balance – biofuels

SWOT analysis



Variability and uncertainty in demand growth escalate globalization of the downstream sector

Strategy objectives



NIS Refining business:

- Health & Safety
- Modern & efficient processes and operations
- Long term profitability based on sustainable development model
- One of the most efficient refineries in South East Europe
- Zero per cent of heavy residues

Development directions



Efficiency

- Increase Operation Availability
- Improve Technology Efficiency
- Increase Energy Efficiency
- Develop Personal Efficiency

New technologies

- Use of conversion-type hydrogenation processes
- Technologies that will allow termination of fuel oil production

Key directions:

Maximize efficiency of existing refinery assets &
Introduce new technologies

HSE Indicators

Block Refining



Health and Safety

Injuries (LTIF):

2006 – 69 injuries in Refinery

2016 – 0 injuries in Refinery


874 days

without Refinery workers injuries!

Our workers increased number of observations and improvement actions to more that **9000/year!!!**



Industrial safety




- Number of maintenance activities on process equipment decreased **68%** after reliability program implementation!

HSE Indicators

Block Refining



Environmental improvement indicators



HSE Training in Refinery

- All Refinery and contractor workers **must be** HSE trained in our Refinery
- There are theoretical and **practical** training for all High risk works
- Our goal is to **improve HSE culture**




HSE Training center in Refinery

Efficiency: key performance indicators




KPIs


Achieved Results



Energy efficiency improved by 35%



Operational unavailability reduced by 47%



Personnel efficiency improved by 67%

Key refinery performance indicators significantly improved

Quartile breaks (Central & Southern Europe)

Key investments



Refinery modernization 1st phase (till 2012)

Mild Hydrocracking Complex (MHC) [completed]

Refinery modernization 2nd phase (till 2019)

Delayed Coker Unit (DCU) [in progress]

Introduction of the new technologies (phase realization)

Fully in line with NIS refining development strategy by 2030

MHC Complex [completed]



Scope

- Mild Hydrocracking complex
- Hydrogen Generating Unit
- Sulphur recovery unit
- Amine regeneration unit
- Sour water stripper unit

Effects

- Increased yield of the diesel and petrol
- Improved quality of the products
- Reduced the content of the sulphur (according to the Euro 5 specification)

Cost/Time


Total cost: App. 500 MM EUR
Realization (EPC phase): 2009-2012

MHC Technology: Chevron
EPCM contractor: CB&I Lummus

Gasoline	Before	After
Sulphur, max, mg/kg	650	10
Benzene, max, % (v/v)	5	1
Total aromatics, % (v/v)	65	35
Pb, mg/l	13	0

Diesel	Before	After
Sulphur, mg/kg	5.000 (avg)	max. 10
Polycyclic aromatics max, % (m/m)	not limited	11

MHC Complex [completed]



MHC/DHT FEED

- Petroleum, Light & Heavy Gas Oil from Crude Distillation Unit
- Vacuum Heavy & Light Gas Oil from Vacuum Distillation Unit

KEY FLOWS

- Unconvertible Oil: Feed to FCC unit
- Low sulphur kerosene: Diesel blending (high quality jet fuel)
- Low sulphur Euro Diesel: High quality product (Euro 5 standard)

MCH: Realized fully in line with NIS refining development strategy

MHC Complex [completed]



Implementation Schedule

№		2006				2007				2008				2009				2010				2011				2012											
		I	II	III	IV	I	II	III	IV	I	II	III	IV	I	II	III	IV	I	II	III	IV	I	II	III	IV	I	II	III	IV								
1	MHC									[Blue bar spanning from Q1 2008 to Q4 2011]																											
2	Design & survey work									[Blue bar spanning from Q1 2008 to Q4 2010]																											
3	Equipment and Materials									[Blue bar spanning from Q3 2009 to Q4 2011]																											
4	Construction and assembly works									[Blue bar spanning from Q1 2010 to Q4 2011]																											
5	Other									[Blue bar spanning from Q1 2008 to Q4 2011]																											

**Project realized within planned budget and projected time frame.
Proved projected process performance**

Delayed Coking Unit (DCU) [in progres]



Scope

New Units

- Delayed Coking Unit
- Amine regeneration unit
- Acid waste water treatment unit

Revamping of existing Units

- MHC/DHT hidro cracking
- Sulphur & Merox Unit

Effects

- Increasing of refinery profitability
- Maximazing high-margin finished products production
- Maximazing process utilization
- Increasing of flexibility (vs. market requirements and constraints)

Cost/Time

Total cost: App. 330 MM US\$

Realization (EPCm phase): 2016-2019


DCU Technology: Lummus Technology

EPCM contractor: TBA

Product yield:

- **Termination of Fuel Oil production**

Delayed Coking Unit (DCU)



DCU Feed

- Vacuum Residue from Vacuum Distillation Unit
- Slurry oil from Fluid Catalytic Cracking Unit.

KEY FLOWS:

- LPG: To LPG storage (after amine washing & caustic treatment)
- Coker Naphtha and Light Coker Gasoil: To DHT;
- Heavy Coker Gasoil: To Mild Hydrocracking (MHC);
- The produced coke: Market (as coke fuel grade)

DCU: Technology optimally selected for closing identified gaps

Delayed Coking Unit (DCU) [in progres]



Implementation Schedule

№		2013				2014				2015				2016				2017				2018				2019															
		I	II	III	IV	I	II	III	IV	I	II	III	IV	I	II	III	IV	I	II	III	IV	I	II	III	IV	I	II	III	IV												
1	DCU					[Blue bar spanning from Q1 2014 to Q4 2019]																																			
2	Design & survey work					[Blue bar spanning from Q1 2014 to Q3 2018]																																			
3	Equipment and Materials									[Blue bar spanning from Q3 2016 to Q3 2018]																															
4	Construction and assembly works													[Blue bar spanning from Q3 2017 to Q4 2019]																											
5	Other					[Blue bar spanning from Q1 2014 to Q4 2019]																																			

Current project status:

- Confirmed Project Economical effectiveness and approved project budget
- Signed Purchase Orders for LLI equipment

Delayed Coking Unit (DCU). Key phases



- Feasibility Study (completed 07/2013)
- FEED CONTRACTOR Selection (completed 02/2015)
- BASIC/FEED Design (completed 02/2016)
- EPCM CONTRACTOR Selection (in progress)
- EPCM (expected duration is 28 months)

Conclusion



- Key business challenges recognized and addressed
- Efficiency improvement program defined and realization started
- First phase of refinery modernization completed
- Competitive position on the market significantly improved
- NIS refinery continues realization of significant investment program despite negative macroeconomic environment