PRISHTINA HEATSAVE DISTRICT HEATING METERING

Burim Hashani

Energy Director Millennium Foundation Kosovo









BACKGROUND

MILLENNIUM FOUNDATION KOSOVO

Millennium Foundation Kosovo is the implementing entity of the \$49 Million Threshold Program agreed between the Government of the Republic of Kosovo and the Millennium Challenge Corporation.

Kosovo Threshold Program addresses two key constraints to Kosovo's economic growth: an unreliable supply of electricity; and real and perceived weakness in the rule of law, government accountability, and transparency

- Reliable Energy Landscape Project
 - Pilot Incentives on Energy Efficiency \$20.6 million
 - District Heating Metering \$10.9 million
 - Independent Power Producer Finance facilitation \$5 million
- Transparent and Accountable Governance Project




PRISHTINA HEATSAVE

MILLENNIUM FOUNDATION KOSOVO

Within the Reliable Energy Landscape Project, the objective of the DHM Activity is to support the reduction of electricity consumption used for heating by introducing quantity-based thermal energy metering on the DH Termokos supply network in Pristina.

Implementing a consumption-based heat metering is expected to:

- Reduce demand on the district heat network;
- Support expansion of heat supply services to new consumers which rely on electricity for heating;
- Improve the services for the consumers who already reside in buildings connected to district heating services; and
- Enable Termokos to transition into consumption-based billing and thus better align their revenues with their costs and the services they provide.






PRISHTINA HEATSAVE

MILLENNIUM FOUNDATION KOSOVO

The aim of these interventions are:

- Installation of measuring equipment in 17,500 apartments to reflect \bullet consumption-based heat metering
- Installation of thermostatic heating valves with built-in balancing \bullet function on radiators.
 - 70,500 Thermostatic valves
 - 51,300 Heat Cost Allocators
 - 4.500 heat meters
 - Support regulator with the design of consumption-based tariffs.
 - Support the Termokos' corporate upgrade transition from spatial billing to consumption-based billing as well as upgrading the consumers database with new software for pricing and billing.



Total Budget

- MFK: \$10.9 million
- Municipality: €2 million

Installation of Metering Systems, Technical Assistance & Heating Tariff Design, BC&O implementation


2022 New contract, Beginning of Installation. Assignment to MP




PRISHTINA HEATSAVE

MILLENNIUM FOUNDATION **KOSOVO** Outline of activities

The Meters, Heat Cost Allocators, Thermostatic Dynamic Valves and the Software start installing




MFK, MCC and the Implementing partners start providing training, capacity building, and regulatory support




Termokos starts applying the new tariffs




MFK, MCC and the Implementing Partners start intensive behavior change campaigns, helping people understand the potential benefits of the new billing system




MFK and MCC conduct monitoring and evaluation of the systems in place





```
Termokos upgrades billing
methodology and customer
         services
```

Environmental and Social Impact Compliance



Gender and Social **Inclusion Compliance**



MILLENNIUM

FOUNDATION

KOSOVO

PRISHTINA HEATSAVE District heating systems in Kosovo

Secondary Network Primary Network JULJU Ħ



Building Substation delimitation point




MILLENNIUM

FOUNDATION

KOSOVO

PRISHTINA HEATSAVE District heating systems in Kosovo


Vertical piping system



Mainly old buildings (60%)



Horizontal piping system




Mainly new buildings (40%)



PRISHTINA HEATSAVE Heat consumption at Vertical Piping System

MILLENNIUM FOUNDATION KOSOVO

Thermostatic Radiator Valves






Thermostatic radiator values are self-regulatingvalues,designedtomaintain a constant temperature in a



PRISHTINA HEATSAVE Heat consumption at Vertical Piping System

MILLENNIUM **FOUNDATION** KOSOVO

Heat Cost Allocators (HCA)





HCA's indirectly estimate the heat consumption of each radiator by measuring the temperature difference between a specified point on the radiator surface and surrounding indoor environment (room) and by taking into account the radiator characteristic coefficients.



PRISHTINA HEATSAVE Project Overview



Decon International is currently implementing consultant whereas IVT consult is Supervising the project

- Baselines studies (HH and Technical)
- Tender Documents
- Institutional, Regulatory and Organizational Measures
- Behavior Change and Outreach Campaigns
- Heat-cost allocation methodology to support consumption-based billing
- Training on Consumption-Based Billing provided to both ERO and Termokos
 - Reviewed by ERO and expected to be in public consultation
- Other GSI and ESP trainings and compliance requirements
- Monitoring and Evaluation




ic consulenten a member of iC group





PRISHTINA HEATSAVE Pricing Methodology-Cap Regulation



| 18 |



MILLENNIUM FOUNDATION KOSOVO

PRISHTINA HEATSAVE Pricing Methodology-Cap Regulation

Fair and transparent – reflect actual measured/estimated heat consumption of the a)

unit.

- Heat metered at thermal substation-level is the main referent measurement of heat supplied to the b) building for which the heat supply company should be compensated;
- The difference between heat measured at building's substation-level and the **C**) aggregated heat consumption of all building's units shall be allocated proportionally to the heating area of each unit;




MILLENNIUM

FOUNDATION

KOSOVO


PRISHTINA HEATSAVE Pricing Methodology-Cap Regulation





MILLENNIUM FOUNDATION KOSOVO

PRISHTINA HEATSAVE Pricing Methodology-Cap Regulation





PRISHTINA HEATSAVE Consumption-Based Billing Methodology



Heat meter	ing level	Metering device and measurement point			
Building-Level metering		Heat Meter at building substation	Measures heat supplied to the building		
Sub-metering	Vertical Piping System	Heat Meter at substation	Measures heat supplied to the building		
	Unit-Level metering through Heat Cost Allocation (HCA)	HCA on the unit's radiators	Allocation of consumed heat between the units		
	Horizontal Piping System Unit-level metering through heat meter	Heat Meter at substation	Measures heat supplied to the building		
		Individual Unit's Heat Meter	Measures the heat supplied to the unit		



PRISHTINA HEATSAVE Individual Customer Heat Invoice

MILLENNIUM FOUNDATION KOSOVO

Thermal Capacity Charge	Common Heat Consumption Charge	Heat Consumption Charge		
TCC = HCU · HCT,[€]	$CUS_{CHC} = US_{CHC} \cdot TET, [\in]$	$HCC = UHC_{MU-L} \cdot TET, [\in]$		
HCU – Thermal Capacity of a Unit (kW) HCT – Heat (Thermal) Capacity Tariff (in €/kW/month)	US _{CHC} – Unit's Share of 'Common Heat Consumption' (kWh) TET – Thermal Energy (Heat) Consumption Tariff (€/kWh)	UHC _{MU-L} – heat consumption of a unit (kWh) that is measured at unit-level; TET – Thermal Energy (Heat) Consumption Tariff (€/kWh)		



PRISHTINA HEATSAVE Ongoing activities



- Negotiations meeting with the new awarded contractor for the supply and installation of the measuring and equipment
- Updated / Compressed Implementation Schedule from implementing contractor.
- Tripartite agreement between Municipality, Termokos, and MFK for assigning the Project after MCC's Threshold Program End Date in September 2022
- Closure plan and assignment to District Termokos/Municipality for the unfinished works by November 2022.

the



MILLENNIUM

FOUNDATION KOSOVO

PRISHTINA HEATSAVE BOQ Heat Distribution equipment

Li	ist of Goo	ods and Services - Delivery Sche	edule (Annex 3)		
Description of Goods + Description of Related Services			Purchaser's Required Delivery Date (as per Incoterms)		Bidder's offered	Final Completion Date(s)
(see chapter 4.7.3 in Section V. Schedule of Requirements)			Earliest Delivery Date	Latest Delivery Date	Delivery date	of Services
Heat distribution equipment (DH substation room, riser pipes)			Estimated Contract signature date: 15.03.2022			
Heat circulation pump - DN40,50,65,60	135 pcs	Prishtina, Kosovo	15.05.2022.	30.09.2022.	Within 6 Months after estimated contract signature date	10 Months after contract signing
Balancing valve - DN25,32,40,50,65,80,100	70 pcs	Prishtina, Kosovo	15.05.2022.	30.09.2022.	Within 6 Months after estimated contract signature date	10 Months after contract signing
Differential pressure control valve - DN25,32,40,50,65,80,100	70 pcs	Prishtina, Kosovo	15.05.2022.	30.09.2022.	Within 6 Months after estimated contract signature date	10 Months after contract signing
Differential pressure control valve - DN32,40,50,65,80,100	60 pcs	Prishtina, Kosovo	15.05.2022.	30.09.2022.	Within 6 Months after estimated contract signature date	10 Months after contract signing
Differential pressure independent control valve - DN25*,32*,40*,50*,65*,80*,100*	35 pcs	Prishtina, Kosovo	15.05.2022.	30.09.2022.	Within 6 Months after estimated contract signature date	10 Months after contract signing



PRISHTINA HEATSAVE BOQ (Heat control and metering

MILLENNIUM **FOUNDATION KOSOVO**

equipment)

Heat control equipment (apartment distribution pipe)						
Thermostatic radiator valve (2-way) with Thermostatic header (based on the technical offer of the bidder)		Prishtina, Kosovo	15.04.2022.	30.09.2022.	Within 6 Months after estimated contract signature date	10 Months after contract signing
Thermostatic radiator valve (3- way)*	50 pcs	Prishtina, Kosovo	15.04.2022.	30.09.2022.	Within 6 Months after estimated contract signature date	10 Months after contract signing
Heat metering/ meter reading collection equipment						
Heat meter (additional cost ultrasonic version)	4,300 pcs	Prishtina, Kosovo	15.06.2022.	30.09.2022.	Within 6 Months after estimated contract signature date	10 Months after contract signing
Heat cost allocators	51,000 pcs	Prishtina, Kosovo	15.04.2022.	30.09.2022.	Within 6 Months after estimated contract signature date	10 Months after contract signing
Parametriziation equipment	5 pcs	Prishtina, Kosovo	15.06.2022.	30.09.2022.	Within 6 Months after estimated contract signature date	10 Months after contract signing
Data collection/ transmission gateway	800 pcs	Prishtina, Kosovo	15.04.2022.	30.09.2022.	Within 6 Months after estimated contract signature date	10 Months after contract signing
Handheld unit (walk-by read-out unit)	5 pcs	Prishtina, Kosovo	15.04.2022.	15.05.2022.	Within 2 Months after estimated contract signature date	10 Months after contract signing



PRISHTINA HEATSAVE BOQ Heat metering and billing system



Heat metering and billing system						
Central metering and billing server station	1 pc	Prishtina, Kosovo	15.04.2022.	15.05.2022.	Within 6 Months after estimated contract signature date	10 Months after contract signing
Printing and enveloping machine	1 pc	Prishtina, Kosovo	15.06.2022.	30.09.2022.	Within 6 Months after estimated contract signature date	10 Months after contract signing
Client PC workstation	4 pc	Prishtina, Kosovo	15.04.2022.	30.09.2022.	Within 6 Months after estimated contract signature date	10 Months after contract signing
Metering and billing software	1 pc	Prishtina, Kosovo	15.04.2022.	30.09.2022.	Within 6 Months after estimated contract signature date	10 Months after contract signing

THANK YOU



